

**PROJECT HOLIDAY INN EXPRESS**



Date of submission 3/28/2018  
 Date of plans 10/30/2017  
 Comments Sheetrock estimate - Drywall, GWB Ceiling  
**TOTAL BASE BID #REF!**

**(718)-717-2729**  
[www.BiddingEnterprise.com](http://www.BiddingEnterprise.com)

SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY.	UNIT	UNIT COST	TOTAL COST
							W/ WASTE			

**09 00 0 FINISHES**

**DRYWALL ASSEMBLIES**

**FIRST FLOOR**

				<b>TYPE M SHAFT WALL - 2HR</b>						
1	A-301	A-104		2 Layers of type X GWB on both sides of wall as;	9216	10%	#####	SF	#REF!	#REF!
				4'x8' GB Sheet			317	Sheets		
				500' Tape Roll			16	Rolls		
				Joint Compound			51	Gallons		
				1-1/4" Drywall Screws			54	Pounds		
2	A-301	A-104		Sound Insulation	2304	10%	2,534	SF	#REF!	#REF!
				<b>TYPE M SHAFT WALL - 1HR</b>						
3	A-301	A-104		1 Layer of 5/8" fire rated GWB on both sides of wall as;	2400	10%	2,640	SF	#REF!	#REF!
				4'x8' GB Sheet			83	Sheets		
				500' Tape Roll			4	Rolls		
				Joint Compound			14	Gallons		
				1-1/4" Drywall Screws			14	Pounds		
4	A-301	A-104		Sound Insulation	1200	10%	1,320	SF	#REF!	#REF!
				<b>TYPE C INTERIOR BEARING WALL - UL U305 - 1HR</b>						
5	A-301	A-104		1 Layer of 5/8" type X GWB on both sides of wall as;	7728	10%	8,501	SF	#REF!	#REF!
				4'x8' GB Sheet			266	Sheets		
				500' Tape Roll			13	Rolls		
				Joint Compound			43	Gallons		
				1-1/4" Drywall Screws			45	Pounds		
6	A-301	A-104		Accoustical Sealant each side	1,288	10%	1,417	LF	#REF!	#REF!
7	A-301	A-104		3" Mineral or glass fibre insulation	3,864	10%	4,250	SF	#REF!	#REF!
8	A-301	A-104		RC-2 Resilient furring channels @ 24" O.C	193	0%	193	EA.	#REF!	#REF!
				<b>TYPE D INTERIOR BEARING WALL - UL U305 - 1HR</b>						
9	A-301	A-104		1 Layer of 5/8" type X GWB on both sides of wall as;	1248	10%	1,373	SF	#REF!	#REF!
				4'x8' GB Sheet			43	Sheets		
				500' Tape Roll			3	Rolls		
				Joint Compound			7	Gallons		
				1-1/4" Drywall Screws			8	Pounds		
10	A-301	A-104		1 Layer of 5/8" sound damping composite GWB as;	624	10%	686	SF	#REF!	#REF!
				4'x8' GB Sheet			22	Sheets		
				500' Tape Roll			2	Rolls		
				Joint Compound			4	Gallons		
				1-1/4" Drywall Screws			4	Pounds		

**PROJECT HOLIDAY INN EXPRESS**



Date of submission 3/28/2018  
 Date of plans 10/30/2017  
 Comments Sheetrock estimate - Drywall, GWB Ceiling  
**TOTAL BASE BID #REF!**

**(718)-717-2729**  
[www.BiddingEnterprise.com](http://www.BiddingEnterprise.com)

SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	UNIT COST	TOTAL COST
11	A-301	A-104		Accoustical Sealant each side	208	10%	229	LF	#REF!	#REF!
12	A-301	A-104		3" Mineral or glass fibre insulation	624	10%	686	SF	#REF!	#REF!
13	A-301	A-104		RC-2 Resilient furring channels @ 24" O.C	31	0%	31	EA.	#REF!	#REF!
				<b>TYPE A INTERIOR NON BEARING WALL</b>						
14	A-301	A-104		1 Layer of 5/8" GWB on both sides of wall as;	192	10%	211	SF	#REF!	#REF!
				4'x8' GB Sheet			7	Sheets		
				500' Tape Roll			1	Rolls		
				Joint Compound			2	Gallons		
				1-1/4" Drywall Screws			2	Pounds		
				<b>TYPE H INTERIOR BEARING WALL - UL U308 - 2HR</b>						
15	A-301	A-104		2 Layers of 5/8" GWB on both sides of wall as;	11280	10%	#####	SF	#REF!	#REF!
				4'x8' GB Sheet			388	Sheets		
				500' Tape Roll			19	Rolls		
				Joint Compound			63	Gallons		
				1-1/4" Drywall Screws			66	Pounds		
16	A-301	A-104		Accoustical Sealant each side	940	10%	1,034	LF	#REF!	#REF!
17	A-301	A-104		3" Mineral or glass fibre insulation	2,820	10%	3,102	SF	#REF!	#REF!
				<b>TYPE B INTERIOR NON BEARING WALL</b>						
18	A-301	A-104		1 Layer of 5/8" type X GWB on both sides of wall as;	8664	10%	9,530	SF	#REF!	#REF!
				4'x8' GB Sheet			298	Sheets		
				500' Tape Roll			15	Rolls		
				Joint Compound			48	Gallons		
				1-1/4" Drywall Screws			51	Pounds		
19	A-301	A-104		Accoustical Sealant each side	1,444	10%	1,588	LF	#REF!	#REF!
20	A-301	A-104		3" Mineral or glass fibre insulation	4,332	10%	4,765	SF	#REF!	#REF!
				<b>TYPE F INTERIOR BEARING WALL - UL U305 - 1HR</b>						
21	A-301	A-104		3 Layers of 5/8" type X GWB as;	936	10%	1,030	SF	#REF!	#REF!
				4'x8' GB Sheet			33	Sheets		
				500' Tape Roll			2	Rolls		
				Joint Compound			6	Gallons		
				1-1/4" Drywall Screws			6	Pounds		
22	A-301	A-104		1 Layer of 5/8" sound damping composite GWB as;	312	10%	343	SF	#REF!	#REF!
				4'x8' GB Sheet			11	Sheets		
				500' Tape Roll			1	Rolls		
				Joint Compound			2	Gallons		
				1-1/4" Drywall Screws			2	Pounds		
23	A-301	A-104		Accoustical Sealant each side	104	10%	114	LF	#REF!	#REF!
24	A-301	A-104		3 1/2" Mineral or glass fibre insulation	624	10%	686	SF	#REF!	#REF!

**PROJECT ADDRESS** HOLIDAY INN EXPRESS



Date of submission 3/28/2018  
 Date of plans 10/30/2017  
 Comments Sheetrock estimate - Drywall, GWB Ceiling

(718)-717-2729

TOTAL BASE BID #REF!

www.BiddingEnterprise.com

SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	UNIT COST	TOTAL COST
				<b>EXTERIOR BEARING WALL</b>						
25	A-301	A-104		1 Layer of 5/8" type X fire rated GWB as;	4464	10%	4,910	SF	#REF!	#REF!
				4'x8' GB Sheet			154	Sheets		
				500' Tape Roll			8	Rolls		
				Joint Compound			25	Gallons		
				1-1/4" Drywall Screws			26	Pounds		
26	A-301	A-104		Accoustical Sealant each side	744	10%	818	LF	#REF!	#REF!
27	A-301	A-104		5 1/2" thick R-19 Insulation	4464	10%	4,910	SF	#REF!	#REF!
				<b>Sub Total</b>						#REF!
				<b>GYPSUM BOARD CEILING</b>						
28	A-601			GWB Ceiling at 8'-0" AFF w/ -RC-2 type resillient channels @ 24" O.C	258	10%	284	SF	#REF!	#REF!
29	A-601			GWB Ceiling at 8'-6" AFF -RC-2 type resillient channels @ 24" O.C	730	10%	803	SF	#REF!	#REF!
30	A-601			GWB Ceiling at 9'-0" AFF -RC-2 type resillient channels @ 24" O.C	1051	10%	1,156	SF	#REF!	#REF!
31	A-601			GWB Ceiling at 10'-0" AFF -RC-2 type resillient channels @ 24" O.C	2560	10%	2,816	SF	#REF!	#REF!
32	A-601			GWB Ceiling at 12'-0" AFF -RC-2 type resillient channels @ 24" O.C	1980	10%	2,178	SF	#REF!	#REF!
				<b>FASCIA</b>						
33	A-601			1'-0" High Fascia	158	10%	174	SF	#REF!	#REF!
34	A-601			1'-6" High Fascia	212	10%	233	SF	#REF!	#REF!
35	A-601			2'-0" High Fascia	420	10%	462	SF	#REF!	#REF!
				<b>INSULATION</b>						
36	A-601	1/A-104		3 1/2" Sound attenuation batts	6439	10%	7,083	SF	#REF!	#REF!
				<b>SUB CEILING</b>						
37	A-601	1/A-104		5/8" Type X fire rated GWB sub ceiling	22102	10%	#####	SF	#REF!	#REF!